REPORT OF ANNUAL INSPECTION OF CCR SURFACE IMPOUNDMENT				
FACILITY NAME: Gorgas Steam Plant – Gypsum Pond				
OWNER/OPERATOR OF FACILITY: Alabama Power Company				
INSPECTION DATE: April 12, 2023				
INSPECTING ENGINEER: Jacob A. Jordan, P.E. (Alabama P.E. License #25093)				
Southern Company Services - Principal Engineer, Dam Safety				
ANY CHANGES IN GEOMETRY OF THE IMPOUNDING			NO	
STRUCTURE SINCE THE PREVIOUS ANNUAL INSPECTION?				
(IF YES, DESCRIBE):				
LOCATION AND TYPE OF EXISTING INSTRUMENTATION			N/A (No instrumentation)	
MAXIMUM RECORDED READING OF EACH INSTRUMENT SINCE PREVIOUS ANNUAL INSPECTION			N/A (No instrumentation)	
APPROXIMATE MINIMUM, MAXIMUM AND PRESENT DEPTH AND ELEVATION OF THE IMPOUNDED				
WATER SINCE PREVIOUS ANNUAL INSPECTION				
MIN. DEPTH: less than 1 foot	MAX. DEPTH: 7 ft		PRESENT DEPTH: N/A	
MIN. ELEVATION: N/A	MAX. ELEVATION: EL 430 ft		PRESENT. ELEVATION: N/A	
APPROXIMATE MINIMUM, MAXIMUM AND PRESENT DEPTH AND ELEVATION OF CCR SINCE				
PREVIOUS ANNUAL INSPECTION.				
MIN. DEPTH: less than 1 ft	MAX. DEPTH: 43 ft		PRESENT DEPTH: N/A	
MIN. ELEVATION: EL 405 ft (est.)	MAX. ELEVATION: EL 448 ft		PRESENT ELEVATION: N/A*	
APPROXIMATE STORAGE CAPACITY OF				
IMPOUNDING STRUCTURE AT TIME OF		1,000,000 cubic yards (with stacking)		
INSPECTION.				
APPROXIMATE VOLUME OF IMPOUNDED		WATER: 0 vd ²	}*	CCR: 0 vd ³ **
WATER AND CCR AT TIME OF INSPECTION				
ANY APPEARANCE OF AN ACTUAL OR POTENTIAL STRUCTURAL				
WEAKNESS OF THE CCR UNIT, IN ADDITION TO ANY EXISTING			NO	
AND APPLIRTENANT STRUCTURES?				
ANY OTHER CHANGE(S) WHICH MAY HAVE AFFECTED THE				
STABILITY OR OPERATION SINCE THE PREVIOUS ANNUAL			NO	
INSPECTION?				
(IF YES, DESCRIBE):				

*The gypsum has been removed from the pond. Any water present in the pond is temporary stormwater retention after rainfall.

**Gypsum removal was completed prior to the inspection. Figures are based on best available data prior to the removal.

Based on the results of the inspection and my review of the data provided, it is my professional opinion that the report has been completed in accordance with 40 CFR 257.83(b) and ADEM Admin. Code r. 335-13-15-.05(4)(b).

A BA James C. Perues, P.E. 16516 PROFESSIONAL

)/17/24 Date

Annual Inspection – Gorgas Steam Gypsum Pond Dam